APPENDIX F

RIGHT-OF-WAY WIDTHS BY MILEPOST ALONG THE PROPOSED BRADWOOD LANDING PIPELINE ROUTE

APPENDIX F

RIGHT-OF-WAY WIDTHS BY MILEPOST ALONG THE PROPOSED BRADWOOD LANDING PIPELINE ROUTE

Begin Milepost	End Milepost	Length (miles)	Construction Method	Right-of-Way Width (feet)
0.0	1.4	1.4	Horizontal Directional Drill (HDD)	100
1.4	3.3	2.0	Trenching	100
3.3	3.7	0.4	HDD	100
3.7	3.8	0.1	Trenching	100
3.8	3.8	<0.1	Trenching through Wetlands	100
3.8	3.8	<0.1	Trenching	100
3.8	3.9	0.1	Trenching through Wetlands	100
3.9	4.0	0.2	Trenching	100
4.0	4.4	0.3	HDD	100
4.4	4.5	0.1	Trenching	100
4.5	4.6	0.1	Trenching through Wetlands	100
4.6	4.9	0.3	Trenching	100
4.9	5.4	0.6	HDD	100
5.4	6.0	0.5	Trenching	100
6.0	6.0	<0.1	Trenching through Wetlands	100
6.0	6.0	<0.1	Trenching	100
6.0	7.0	0.9	Trenching through Wetlands	100
7.0	7.9	1.0	Trenching/Topsoil	120
7.9	8.0	0.1	Trenching through Wetlands	100
8.0	8.2	0.1	Trenching	100
8.2	8.2	<0.1	Trenching through Wetlands	85
8.2	8.4	0.2	Trenching	100
8.4	8.4	<0.1	Trenching through Wetlands	100
8.4	8.4	<0.1	Trenching/Topsoil	120
8.4	8.6	0.2	HDD	100
8.6	8.7	<0.1	Trenching through Wetlands	100
8.7	8.7	<0.1	Trenching/Topsoil	120
8.7	8.8	0.1	Trenching through Wetlands	100
8.8	8.8	0.1	Trenching/Topsoil	120
8.8	8.9	0.1	Trenching through Wetlands	100
8.9	8.9	<0.1	Trenching/Topsoil	120
8.9	8.9	<0.1	Trenching through Wetlands	100
8.9	9.0	<0.1	Trenching/Topsoil	120
9.0	9.0	<0.1	Trenching through Wetlands	100
9.0	9.0	<0.1	Trenching/Topsoil	120
9.0	9.0	<0.1	Trenching through Wetlands	85
9.0	9.1	0.1	Trenching/Topsoil	120
9.1	9.1	<0.1	Trenching through Wetlands	85
9.1	9.1	<0.1	Trenching/Topsoil	120
9.1	9.1	<0.1	Trenching through Wetlands	85
9.1	9.1	<0.1	Trenching/Topsoil	120
9.1	9.2	<0.1	Trenching through Wetlands	85
9.2	9.2	<0.1	Trenching/Topsoil	120
9.2	9.2	<0.1	Trenching through Wetlands	100
9.2	9.2	<0.1	Trenching/Topsoil	120
9.2	9.2	<0.1	Trenching through Wetlands	85
9.2	9.2	<0.1	Trenching/Topsoil	120

RIGHT-OF-WAY WIDTHS BY MILEPOST ALONG THE PROPOSED BRADWOOD LANDING PIPELINE ROUTE

Begin Milepost	End Milepost	Length (miles)	Construction Method	Right-of-Way Width (feet)
9.2	9.2	<0.1	Trenching through Wetlands	100
9.2	9.4	0.2	Trenching/Topsoil	120
9.4	9.5	<0.1	Trenching through Wetlands	85
9.5	9.5	<0.1	Trenching/Topsoil	120
9.5	9.5	0.1	Trenching through Wetlands	100
9.5	9.7	0.2	Trenching/Topsoil	120
9.7	9.7	<0.1	Trenching through Wetlands	85
9.7	9.7	<0.1	Trenching/Topsoil	120
9.7	9.7	<0.1	Trenching through Wetlands	85
9.7	9.8	0.1	Trenching/Topsoil	120
9.8	9.8	<0.1	Trenching through Wetlands	85
9.8	9.8	<0.1	Trenching/Topsoil	120
9.8	9.8	<0.1	Trenching through Wetlands	120
9.8	9.8	0.1	Trenching/Topsoil	120
9.8	9.9	<0.1	Trenching through Wetlands	85
9.9	9.9	<0.1	Trenching through Wetlands	100
9.9	9.9	<0.1	Trenching/Topsoil	120
9.9	10.0	0.1	Trenching through Wetlands	100
10.0	10.1	0.2	HDD	100
10.1	10.5	0.3	Trenching/Topsoil	120
10.5	10.5	<0.1	Trenching through Wetlands	100
10.5	10.8	0.3	Trenching/Topsoil	120
10.8	10.8	0.1	Trenching through Wetlands	100
10.8	11.0	0.2	Trenching/Topsoil	120
11.0	12.6	1.6	Trenching	100
12.6	12.7	0.2	Trenching/Topsoil	120
12.7	12.7	<0.1	Trenching through Wetlands	85
12.7	12.8	<0.1	Trenching/Topsoil	120
12.8	12.8	<0.1	Trenching through Wetlands	100
12.8	12.8	0.1	Trenching/Topsoil	120
12.8	12.8	<0.1	Trenching through Wetlands	100
12.8	12.9	<0.1	Trenching/Topsoil	120
12.9	13.0	0.1	Trenching through Wetlands	100
13.0	13.1	0.1	Trenching/Topsoil	120
13.1	13.2	0.1	Trenching through Wetlands	100
13.2	13.4	0.3	HDD	100
13.4	13.5	0.1	Trenching	100
13.5	13.5	<0.1	Trenching through Wetlands	85
13.5	18.1	4.6	Trenching	100
18.1	18.1	<0.1	Trenching through Wetlands	85
18.1	18.2	<0.1	Trenching	100
18.2	18.2	<0.1	Trenching through Wetlands	85
18.2	18.2	<0.1	Trenching through Wetlands	100
18.2	18.2	<0.1	Trenching through Wetlands	85
18.2	18.3	0.1	Trenching through Wetlands	100
18.3	18.4	0.1	Trenching	100

RIGHT-OF-WAY WIDTHS BY MILEPOST ALONG THE PROPOSED BRADWOOD LANDING PIPELINE ROUTE

Begin Milepost	End Milepost	Length (miles)	Construction Method	Right-of-Way Width (feet)
18.4	18.6	0.3	Trenching through Wetlands	100
18.6	18.6	<0.1	Trenching	100
18.6	18.8	0.2	Trenching through Wetlands	100
18.8	18.8	0.1	Slick Bore	100
18.8	19.0	0.1	Trenching	100
19.0	19.8	0.8	HDD	100
19.8	20.3	0.5	Trenching	100
20.3	20.8	0.5	HDD	100
20.8	21.2	0.4	HDD	100
21.2	22.3	1.1	Trenching	100
22.3	22.4	0.1	HDD	100
22.4	22.5	0.1	Trenching/Topsoil	120
22.5	22.8	0.2	Trenching	100
22.8	22.9	0.1	Trenching/Topsoil	120
22.9	23.0	0.2	Trenching	100
23.0	23.1	0.1	Trenching/Topsoil	120
23.1	27.7	4.6	Trenching	100
27.7	28.0	0.3	Trenching/Topsoil	120
28.0	31.8	3.8	Trenching	100
31.8	32.2	0.4	Trenching/Topsoil	120
32.2	34.2	2.0	Trenching	100
34.2	34.6	0.4	HDD	100
34.6	34.9	0.2	Trenching/Topsoil	120
34.9	35.3	0.5	HDD	100
35.3	36.3	0.9	Trenching	100